

BRUHATH BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE ELECTRICAL DIVISION

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule B"

Name of the work : Providing illumination in Ramachandrapura Junction and Gangamma Circle in jalahalli police Limit Ward No 10.(Nanjappa Circle,Doddabhommasandra circle)

Sl.No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In words
1	14	Fabricating, supplying and erecting swaged tubular pole of height ...Mtr having three sections, and providing two coats of red oxide paint and finished with two coats of enamelled paint of approved quality and colour and M.S. base plate of suitable size welded at the bottom of the pole(as per IS) and 40mm dia GI / flexible PVC pipe of 1 mtr length fitted to the heavy gauge polycarbonate control box including 5way connector of size 167x125x82mm for 7.5M pole/200x160x98mm for remaining length of pole with front opening cover, with locking arrangements and suitable capacity MCB / DP switch. The pole shall be erected in cement concrete work (1:2:4) including excavation and refilling of planting depth of the pole to the ground level and the coping CC shall be up to 0.6M above ground level as per IS 2713 - 7. Erection of heavy duty pole on Footpath / median 9Mt (5Mt Hb, 165.1mm dia 4.85mm thick x2M Hm, 139.7mm dia 4.50mm thick x 2M Ht, 114.3mm dia 3.65mm thick) as per IS 410 SP 32	Nos	11000.00	Rupees Eleven Thousand Only
2	12	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with... W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in- house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source. LED Floodlight 200W	Nos	13000.00	Rupees Thirteen Thousand Only
3	62	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source. LED Streetlight 120 Watts	Nos	7300.00	Rupees Seven Thousand Three Hundred Only

For SHREE VINAYAKA ELECTRICALS

V. Lakshmi
Proprietor

4	8	Supplying and fixing telescopic M.S. bracket fabricated by using 0.5m length 4" dia telescopic M. S. pipe, with 2" dia 1.5m long M. S. bracket and are welded with suitable angle, using 6mm thick M. S. sheet, grip bolts & nuts, as required, suitable for 9 to 12 Mtrs. M. S. tubular pole, with necessary two coats of painting, with all other accessories. Single bracket 1.5 Mtr. Length		800.00	Rupees Hundred
5	40	Supplying and Fixing of. mm dia class A GI pipe bracket up to 2 Mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires. Using 32mm dia G.I.Pipe	Nos	730.00	Rupees Seven Hundred Thirty Only
6	52	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires.	Each	100.00	Rupees One Hundred Only
7	190	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 5) 3.5 core 25 sqmm	Mtr	100.00	Rupees One Hundred Only
8	190	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. 7) 25 sqmm to 75 sqmm	Rmt	30.00	Rupees Thirty Only
9	140	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. (As per Civil SR KSRB I-2, P-7) 2) In soil (ordinary)	Mtrs	70.00	Rupees Seventy Only
10	40	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. 2) 50x50x6mm	Per Mtr	300.00	Rupees Three Hundred Only
11	4	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE, 1) 100Amps 25kA.	Each	4000.00	Rupees Four Thousand Only
12	4	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility. 300mmx300mmx214mm	Each	3000.00	Rupees Three Thousand Only
13	600	Stringing of 1.1KV grade aerial bunched 3 core cable of XLPE insulation of size (3x95) (for Phase conductor) + (1x70) (insulated messenger neutral) + (1x25) for street light control.	Mtrs	20.00	Rupees Twenty Only
14	20	RCC Pole clamp - MS (Dwg No. BESCOM/GM/QS&S/30 Dtd 24.11.2018)	Nos	48.00	Rupees Forty Eight Only
15	20	Fixing of 2 Pin cross arm with insulator and Braces fixing	Nos	80.00	Rupees Eighty Only
16	40	Supplying of Piercing Connector Suitable for 16 Sqmm - 95 Sqmm AB Cable - Street Light Connections	Nos	100.00	Rupees One Hundred Only
17	4	Supplying of Dead End Clamp/Anchor Clamp Assembly 25 to 95 Sqmm Bare Messenger (Exclusive of pole clamp and eye hook)	Nos	100.00	Rupees One Hundred Only
18	40	Installation of Insulation piercing connector for main to street light Main : 16-95sqmm, Tap : 1.5-10sqmm (EP95)	Nos	30.00	Rupees Thirty Only
19	4	Fixing of Universal/ Dead end Hook	Nos	100.00	Rupees One Hundred Only

For SHREE VINAYAKA ELECTRICALS

V. Lakshmi
Proprietor

19	Supply of Suspension Clamp Assembly 16 to 70 Sqmm Bare Messenger(Exclusive of pole clamp and eye hook) 284845 No	Nos	120.00	Rupees One Hundred Twenty Only
21	Erection of Suspension Clamp - 25 to 95 sqmm bare messenger		100.00	Rupees One Hundred Only
22	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.2 X 25 + 1 X 25 SQ.MM	Per Mtr	100.00	Rupees One Hundred Only

For SHREE VINAYAKA ELECTRICALS

V. Jayaram
Proprietor

[Signature]
EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone